



Builtline Construction

4th Main Rd, CA's, near lingaraj Pujari & Co,
Malleshwaram, Bengaluru, Karnataka
560003

Builder's Promise

- A detailed architectural plan will be provided by our in-house architect at no additional cost, ensuring thoughtful design, efficient space planning, and full compliance with building standards.
- All payments will follow a clear, milestone-based schedule, giving you complete transparency and control at every stage of construction.
- This is a comprehensive Turnkey Contract. Builtline Construction assumes total responsibility for design, material procurement, site execution, and final handover, with no hidden costs or unexpected charges.
- We are committed to delivering only the highest quality, using trusted brands, skilled professionals, and strict on-site quality checks to ensure long-lasting strength and finish.
- Dedicated quality inspections, including regular Ready Mix Concrete (RMC) testing and raw material checks, guarantee that your structure meets IS standards and industry best practices.
- Should there be any delay beyond the agreed-upon timeline, Builtline Construction will pay ₹50,000 as compensation for the delay. a promise of our accountability and respect for your time.
- We stand by our pledge of timely delivery, robust structural quality, and your complete peace of mind, because your trust is our greatest asset.
- Builtline Construction proudly brings over 9 years of experience in delivering high-quality residential and commercial projects, earning trust through consistent workmanship and timely completion.
- We believe in long-term relationships, even after handover, our team remains available for any genuine support or guidance you may need regarding your new home.



Builtline Construction

4th Main Rd, CA's, near lingaraj Pujari & Co,
Malleshwaram, Bengaluru, Karnataka
560003

OWNER'S SCOPE:

- **BWSSB Permission:** The Owner shall obtain all necessary approvals from BWSSB for water connection, drainage, and sewerage system prior to commencement of construction.
- **KEB Permission & Meter:** The Owner shall apply for and secure electricity supply permissions from KEB, including the sanction and installation of a temporary/permanent electricity meter.
- **BBMP Permission:** The Owner is responsible for acquiring relevant clearances from BBMP for site development, construction activities, and municipal compliance as applicable.
- **BBMP Plan Approval:** The Owner shall ensure submission and approval of sanctioned building plans from BBMP, including any necessary modifications and updates as per regulatory norms.
- **Lift area:** inside wiring and earthing.
- **Provision of Water and Electricity for Construction:** The Owner shall ensure the continuous availability of water and electricity on-site, required for civil, structural, and finishing works during the construction phase.



Builtline Construction

4th Main Rd, CA's, near lingaraj Pujari & Co,
Malleshwaram, Bengaluru, Karnataka
560003

Construction Material Specifications and Details

1. Package Specifications

- Package Name: Standard Package
- Package Rate: ₹ 2,000.00 per sq. ft
- Project Type:
- Total Built-up Area:

2. Design & Drawings (Include all Floors)

All design files will be shared in non-editable PDF format. The following will be included:

- 2D Floor Plan
- Structural Design
- 3D Elevation Design
- Reinforcement
- Shuttering

3. Structural & Construction Specifications (Include all Floors)

- Aggregates: 20 mm & 40 mm.
- Sand
 - M-Sand for block work, columns and Roof.
 - P-Sand for plastering.
- RCC Design Mix: As per the certified structural designer's recommendations.
- Waterproofing
 - Waterproofing in the terrace slab, all washrooms and balconies will be done using Fosroc Brushbond or equivalent.
- Ceiling Height
 - 10 feet (Finished Floor Level to Finished Floor Level).
 - 10-12 feet (For Duplex House).
- Foundation
 - As per the structural drawings.
 - Additional foundation may be required based on soil conditions (Cost extra).
- Walls
 - Solid concrete blocks to be used for outer and partition walls.
 - PCC of 100 mm to be laid below the ground floor flooring.



Builtline Construction

4th Main Rd, CA's, near lingaraj Pujari & Co,
Malleshwaram, Bengaluru, Karnataka
560003

- Plastering
 - Internal Plaster: 1:5 cement mortar.
 - External Plaster: 1:5 cement mortar.
 - Ceiling Plaster: 1:4 cement mortar.
 - Plaster thickness: 12 mm.
 - Chicken mesh to be used at beam-column and masonry wall junctions.
- Additives & Compounds
 - Fosroc or equivalent waterproofing and plaster admixtures.
- Materials
 - Steel: Steel A-one Gold.
 - Blocks: 6" solid blocks for exterior walls and 4" for Partition walls (Lab approved).
 - Cement: ACC, Ultratech or equivalent (Grade 43 & 53).
- Column & Beam Dimensions
 - Columns: Based on the Structural Design.
 - Beams: Based on the Structural Design.

4. Excavation & Foundation Conditions

- Foundation
 - In cases of wet soil, loose soil or rocky layers, extra charges will apply as per the structural engineer's recommendation. (if exceeds excavation depth)
- Individual Foundation
 - The depth is considered as per the design.
- Unspecified Items
 - Any item not explicitly mentioned in this specification is excluded from the scope.
- Finished Floor Level (FFL)
 - The quotation includes raising the ground floor FFL to 1.5 feet above the existing ground level.
- Transportation of Excavated Earth - included in the package.
- Waste Debris Removal - Disposal of construction waste is included.
- Solar Plumbing - Provision for all bathrooms is included.
- Sewage Chambers
 - Fitted with FRP cover lids as per site requirements.



Builtline Construction

4th Main Rd, CA's, near lingaraj Pujari & Co,
Malleshwaram, Bengaluru, Karnataka
560003

5. Kitchen & Utility Provisions

- Kitchen Area
 - Kitchen Sink: Premium Quality Quartz Material (₹5,000/-).
 - Water purifier inlet near the sink.
 - Washing machine inlet and outlet (in utility or dry balcony – can be relocated to terrace).
 - 20mm thick quartz (150/- per sqft).
 - Exhaust/chimney point.
 - Dishwasher inlet and outlet.
- Utility Area
 - Will include a dedicated water inlet and outlet.
 - Kitchen and utility area taps will be of Jaguar/Cera.
 - Utility sink & faucet: Up to ₹3,000.
 - All other faucets & accessories will be ISI marked.

6. Bathroom Specifications

- Accessories Included
 - European water closet for all toilets (Floor Mount Commode).
 - All bathrooms will have one diverter or wall mixer, 1 shower system, 2 taps, 1 washbasin & 1 geyser point.
- Bathroom Doors
 - WPVC Doors.
- Tile Work & Fillings
 - Spacer joints will be provided for tile installations.
 - Tile filling with polymeric cement grout (Roff).
 - Gratings are sealed with the same grout for durability.
- Piping & Fittings
 - External pipes will be installed on raised clamps.
 - Sewer line connection to the main drain line is included.
- Bathroom Wall Tiles
 - Up to 7 ft height; value up to ₹40 + ₹20 per sq. ft.
- Piping Brands
 - CPVC Pipes: Ashirwad / Supreme.
 - PVC Pipes: Ashirwad / Supreme.
 - Solar and geyser water line provision included.



Builtline Construction

4th Main Rd, CA's, near lingaraj Pujari & Co,
Malleshwaram, Bengaluru, Karnataka
560003

7. Doors & Windows

- Windows
 - Wooden frames with single-glass shutters.
- Main Door
 - Fitted with a premium lock.
 - Includes:
 - 2 tower bolts
 - 4 hinges
- Timber Quality
 - Only well-seasoned, knot-free, warp-free, crack-free, and accurately glued timber will be used for all woodwork.
 - All woodwork will receive two coats of paint.
- Windows & Ventilators
 - The opening area (including frames) is calculated as 10% of the total built-up area.
 - Window Chejja: Provides up to 1 ft outward projection + 6 inches extra on each side of the window.
- Door/Window Shutter and Frame Specifications
- Shutters
 - Main Door: 3.6 ft × 8 ft (Teak wood)
 - Room Doors: 3 ft × 7 ft (Flush doors with laminates)
 - Pooja Room: 3.6ft X 7 ft (Teak wood)
 - Bathroom Doors: 2.6 ft × 7 ft (WPVC)
 - Windows: Based on design plan (Sal/mahogany wood)
- Frames Thickness
 - Main Door Frame: 6 inch × 4 inch (Teak wood)
 - Pooja room: 6 inch X 4 inch (Teak wood)
 - Room Door Frames: 3 inch × 5 inch (Sal/mahogany wood)
 - Bathroom: 3 inch × 5 inch (WPVC)
 - Windows: 3 inch × 5 inch (Sal/mahogany wood)



Builtline Construction

4th Main Rd, CA's, near lingaraj Pujari & Co,
Malleshwaram, Bengaluru, Karnataka
560003

8. Painting Specifications

- External Walls:
 - 1 coat of primer + 2 coats of exterior-grade paint.
- Internal Walls & Ceilings
 - Wall putty for a smooth finish.
- Interior Paint System
 - Birla Wall Putty.
 - Tractor Emulsion Paint.
- Exterior Paint System
 - Ace paint.
- MS Steel Works
 - Enamel paint to be used for window grills and railings.
 - All MS steel will be coated with an anti-corrosion primer before painting.

9. Flooring & Wall Tile Specifications

- Wall Tiles
 - All ceramic tiles shall be free from cracks, chips, spots or grazes.
 - Dimensional variation allowed: 1 to 1.5 mm.
 - Minimum tile thickness: 6 mm (as per specifications).
- Granite Flooring
 - Granite must be sound, crack-free and free of patches, flaws or veins.
 - Minimum thickness of granite: 20 mm.
- Tile Installation
 - All wall tiles will be fixed using tile adhesive.
 - Tile joints shall be thoroughly cleaned and grouted with site-mixed grout.
 - Grouting in balconies and terraces shall use polymeric cement grout.
- Other Notes
 - Flooring, dado and skirting must be perfectly levelled.
 - Skirting: Tile or granite with a minimum height of 75 mm.
 - Laying of granite and wall tiles is included in the package.
 - Italian marble or marble (if opted) will incur additional charges (including chemical polishing & laying).

10. Flooring Finishes

Area	Material	Value
Living & Dining	Granite	₹80 + ₹25
BedRooms	Granite	₹80 + ₹25
Kitchen Flooring	Granite	₹80 + ₹25
Bathroom Wall Tiles	Tiles	₹40 + ₹20
Balcony Flooring	Anti-skid Tiles	₹40 + ₹20
Staircase Internal Flooring	Granite	₹80 + ₹25
Staircase External Flooring	Granite	₹80 + ₹25
Pooja Room	Granite	₹60+ ₹25
Parking Area	Anti-skid Tiles	₹40 + ₹20

- **Note:** Granite/Italian Marble is considered as owner's choice. Cost shall be assigned accordingly. Only Granite/Tiles & laying cost is included in the package.
 - Marble/Italian marble laying cost (labour + material) is not included and shall be borne by the owner.
 - Steps: A 20mm edge polish shall be done. Skirting (75 mm) for living areas will be included as per the package.
 - Any additional borders, steps or stands in marble/granite/tiles will be charged extra based on labour and material.



Builtline Construction

4th Main Rd, CA's, near lingaraj Pujari & Co,
Malleshwaram, Bengaluru, Karnataka
560003

11. Electrical Works

- Wiring: Anchor fire-resistant wires shall be used.
- Television Cable Provision: Provided in all bedrooms and living areas.
- Power Points: Light and plug points shall be provided as per requirements around the house.
- UPS Provision: Will be done.
- The earthing & panel box will be included.
- Electric Vehicle Charging: Point Provision in the parking area will be done.
- MCB Board: Provided using Schneider, Legrand or equivalent brands.
- Switches & Sockets: Hifi/GM model switches (as per package).
- CCTV Points.

12. Miscellaneous

- Main Gate:
 - included in the package.
 - Mild steel construction of approved design.
- Compound Wall (included in the package if provided)
 - Cement block masonry.
 - 115 mm thickness.
- Bathroom
 - Step-up model as per the package.
 - Sunken bathroom with branded sanitary models included in the package.
- External Electrical Work
 - Electrical Panel Box will be included.
 - Expansion Joints Will be provided wherever necessary.
- Foundation for Compound Wall
 - Stone masonry.
 - Minimum width: 450 mm (1.5 ft).
 - Minimum depth: 600 mm (2 ft).
 - Foundation laid on compacted hard soil.
 - Bed concrete: Minimum 80 mm thickness.
- Compound Wall Finish
 - Plastered and painted as per plastering and painting specifications.
- Weatherproofing
 - One coat of waterproofing (Dr. Fixit or equivalent) at the terrace level.
- Cement
 - PPC and OPC cement to be used for both structural and non-structural works.



Builtline Construction

4th Main Rd, CA's, near lingaraj Pujari & Co,
Malleshwaram, Bengaluru, Karnataka
560003

13. Additional Civil Works and Provisions

- Parapet Wall
 - To be constructed with a height of 3 feet.
- Underground Sump
 - Constructed using RCC & Internal plastering will be done.
 - Includes FRP cover plate.
 - Waterproofing chemicals will be applied to the plaster mortar.

14. Miscellaneous Provisions

- Fabrication work: External (MS) and internal railings (SS).
- Water Storage
 - Overhead tank: 1000 L - 3000 L tanks, based on the number of floors and site measurement.
 - Underground sump: 10,000 - 18,000 litres. Based on the number of floors and the site measurement.
- Dewatering
 - Included if required during excavation or backfilling.

15. Complementary work

- Gas line.

